

NOTES


1. TANKS SHOULD BE GIVEN HYDRAULIC PRESSURE TEST PRIOR TO INSTALLATION & BEFORE PROTECTIVE COAT IS APPLIED THE TEST SHOULD BE MAINTAINED AT A CONTROLLED PRESSURE OF 0.36 KG/CM FOR 2 HOUR.
2. BACK FILLING OF THE EARTH SHOULD BE CARRIED OUT SIMULTANEOUSLY OUTSIDE & INSIDE THE RCC WALL
3. RCC BEAM SHOULD BE CAST FIRST BEFORE LAYING CC BASE
4. PROVIDE CLEAR COVER TO MAIN REINFORCEMENT
5. FOR 25mm FOR SLAB
6. # REPRESENTS TOR
7. ALL DIMENSIONS ARE IN mm UDS.



WITH HOLDING DOWN ARRANGEMENT DETAIL



CROSS SECTION B-B
45 KL EARTHPIT TANK



Bharat Petroleum Corporation Ltd

DRN.

DATE :

SCALE : 1:10

CKD BY:

DRG.NO:E&P.RET.T1.03

JOB NO.: BPCL